

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>21</u> T. <u>19</u> N. S., R. <u>6</u> E. W.		16; 7; 6
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 5, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**C. Continued:**

XX

6

Drove 5/8"x 34" re-rod w/RLS cap;  
 set cedar post w/loc tag  
 10" Black Oak            N75°W            67.85'  
 7" Black Oak            N25°W            63.55'  
 18" Twin Black Oak    N35°E            46.20'  
 Fd 1" pipe (flush)    N14°29'E        76.05'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 16 - Established SE Cor. of W $\frac{1}{2}$  of SE $\frac{1}{4}$  of Section 21 per standard B.L.M. instructions.
- 7 - Found and accepted 3/4" iron pin (in N-S bit. road) for N 1/8 Cor. on East line of Section 21.
- 6 - Established center of NE $\frac{1}{4}$  of Section 21 per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>16</u> Set 5/8"x34" re-rod w/RLS cap & cedar post w/loc tag	<u>7</u> Found 3/4" iron pin	
7" Black Oak    N55°W    21.4'	Power Pole    N20°W    90.94'	
4" White Pine    N5°W    77.3'	Power Pole    S10°W    129.27'	
5" Maple        S30°E    15.2'	S'ly railroad rail    Due N    20.6'	
	Set ced post w/loc tag    Due W    33'	
	Ctr bit road        Due E    2'	

SIGNED BY Carl F. Roser 01-06-86 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

REDDING TWP  
CLARE COUNTY

Reproduced by the State of Michigan