


LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970
 Page 2 of 2

For Corners In:			
Clare	Located in		Corner Code #
(County)			
1. Public Land Survey	T <u>19N</u> R <u>6W</u>		<u>G7</u>
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			



I, Craig W. McVean, in a field survey on Oct. 4, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7							●						
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. See Page 1

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G7 – Sec. Corner common to Sec. 15, 16, 21 & 22 – Excavated Bit. Rd. intersection based on retracement of 1889 & 1899 plats and find 1 3/4" O.D. iron pipe 1.9' below bit. surface. This pipe is the most historical position of the corner and agrees with the 1889 & 1899 plat monumentation found North and West of the corner per County Surveyors F. Trumbull (Osceola Co.) and D. E. Teed (Wexford Co.) at the time. Both Trumbull and Teed were very reputable surveyors in their time. I cannot question their perpetuation of this corner position. 1 3/4" pipe accepted as the best available evidence of the position of the original corner.

- Reference Pt. 'A' – Fd. Plastic cap #33977 in Mon. Box is S10°39'W 5.89' from 'G7'. This appears to be a position established by A. D. Johnson in 1911 and used by MDOT, Lapham, Urbaniak, McClung, Sedgman, Roser & Robison per their LCRC's, plats and Record surveys since 1961. Could not accept Johnson position because it doesn't fit 1889 & 1899 plats. CIR #33977 in Mon. Box not utilized as 'G7' in this survey.

- Reference Pt. 'B' – Based on retracement of 1957 plat by W. S. Moore his position would be S49°04'E 3.20' from 'G7'. No iron here now but this position would agree closely with 5/8" iron noted by Roser as Witness #12 on his LCRC. Moore position not accepted as 'G7' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G7 – Drove stamped 2 1/2" Brass Cap on 5/8" x 34" rebar into found 1 3/4" O.D. Iron pipe. Add Mon. Box.
 N69°E 66.10' to set nail & tag in SE side 22" Oak
 S63°W 67.12' to set nail & tag at old nail in NW side 12" J. Pine (#7)
 S47°E 60.85' to set nail & tag in NE side 5" Oak
 N76°W 86.70' to set nail & tag in S side 14" Oak in clp.
 S10°39'W 5.89' to Ref. Pt. 'A' – CIR in Mon. Box
 S49°04'E 3.20' to Ref. Pt. 'B' – Calc. position only.



Signed by: Craig W. McVean Date: 5/26/2009
 Surveyor's Michigan License No.: 39088