LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Clare
(County)

Located In — Corner Code #

1. Public Land Survey — T _____ R _____ _____
   T _____ R _____ _____
2. Property Controlling in Section — S 3 T 19N R 6W 12
   S 3 T 19N R 6W 13
3. Miscellaneous Property in Section — S _____ T _____ R _____ _____
   S _____ T _____ R _____ _____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept. 10, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

12 – None

13 – None.

STATE OF MICHIGAN
CRAIG W. McVEAN
PROFESSIONAL SURVEYOR
No. 39088
LICENSED PROFESSIONAL SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

12 – CS 1/16 Corner, Section 3 - Set a stamped 2" Aluminum cap on 5/8" x 34" rebar per Standard BLM procedure.

13 – SE 1/16 Corner, Section 3 - Set a stamped 2" Aluminum Cap on 5/8" x 34" rebar per Standard BLM procedure. Corner falls in N. Track of Sand 2-track.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12 – Stamped 2" Aluminum cap on 5/8" x 34" rebar
S55°W 31.93' to set nail and tag in Northwest side 4" White Pine
S38°E 40.49' to set nail and tag in East side 4" White Pine
N59°E 10.92' to set nail and tag in Northwest side 5" White Pine
N16°W 87.19' to set nail and tag in West side 13" Red Oak
Set Blue Carsonite Post with location tag 1' South

13 – Stamped 2" Aluminum cap on 5/8" x 34" rebar
N26°E 84.47' to set nail and tag in West side 8" Oak
S66°E 31.22' to set nail and tag in East side 12" White Pine
S69°W 70.96' to set nail and tag in South side 6" Jack Pine
N35°W 65.39' to top of blow off valve for gas well
Set a Blue Carsonite Post with location tag 5' North

Signed by: Craig W. McVean Date: 5/26/2009

Surveyor's Michigan License No.: 39088

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1971
Revised May 14, 1975
Revised Jan. 1983
Revised Oct. 1995