

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Clare Located In _____ Corner Code # _____
 (County)

- | | | | | |
|--------------------------------------|-------------|--------------|-------------|-----------|
| 1. Public Land Survey | | T _____ | R _____ | |
| | | T _____ | R _____ | |
| 2. Property Controlling in Section | S <u>10</u> | T <u>19N</u> | R <u>6W</u> | <u>8</u> |
| | S <u>10</u> | T <u>19N</u> | R <u>6W</u> | <u>11</u> |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct 2, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

8 – None

11 – No date – Unrecorded survey by Gourdie-Fraser. Shows corner.



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

8 – CW 1/16 Corner Section 10. Set a stamped 2" Aluminum cap on a 5/8" x 34" rebar per Standard BLM procedure.

11 – SW 1/16 Corner Section 10 - Set a stamped 2" aluminum cap on a 5/8" x 34" rebar per Standard BLM procedure. North 50'± to centerline E-W 2-track. S57°18'W 61.53' from '11' found 1/2" rebar that appears to be the position per the unrecorded Gourdie-Fraser survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8 – Stamped 2" Aluminum cap on a 5/8" x 34" rebar.
 N40°E 16.45' to set Nail & Tag in NW side 11" White Pine
 West 8.44' to set Nail & Tag in S. side 12" White Pine
 S30°E 48.10' to set Nail & Tag in NE side 13" White Oak
 N14°E 42.26' to set Nail & Tag in E. side 18" Twin White Oak
 Set Blue Carsonite Post with location tag 1' East

11 – Stamped 2" Aluminum cap on a 5/8" x 34" rebar
 West 58.56' to set Nail & Tag on S. side 12" Oak
 S33°E 23.71' to set Nail & Tag on NE side 10" White Pine
 N54°E 45.06' to set Nail & Tag on SE side 6" Oak
 N03°E 78.93' to set Nail & Tag on W. side 11" White Pine
 Set Blue Carsonite Post with location tag 1' Northeast
 S57°19'W 61.53' to found 1/2" rebar

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/26/2009