

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Clare Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |             |              |             |                |
|--------------------------------------|-------------|--------------|-------------|----------------|
| 1. Public Land Survey                | T _____     | R _____      |             |                |
|                                      | T _____     | R _____      |             |                |
| 2. Property Controlling in Section   | S <u>15</u> | T <u>19N</u> | R <u>6W</u> | <u>3</u>       |
|                                      | S <u>15</u> | T <u>19N</u> | R <u>6W</u> | <u>NN 1/64</u> |
| 3. Miscellaneous Property in Section | S _____     | T _____      | R _____     |                |
|                                      | S _____     | T _____      | R _____     |                |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Feb. 27, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

3 - None NN 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

3 - N 1/16 Corner common to Section 15 & 16, T19N, R6W – Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. NN 1/64 – Cor. Common to Sec. 15 & 16 – being the SW Corner of the N 1/2 of the NW 1/4 of the NW 1/4 of Sec. 15, T19N, R6W – Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3 – Stamped 2" Alum. Cap on 5/8" x 34" rebar  
 N33°E 39.17' to set nail & tag in E. side 30" W. Pine  
 N42°W 31.41' to set nail & tag in NE side 14" Cedar  
 N86°W 27.33' to set nail & tag in S. side 11" Cedar  
 S40°E 37.56' to set nail & tag in SW side 12" Hemlock  
 Set Blue Carsonite Post with loc. tag 2' South

NN 1/64 – Stamped 2" Alum. Cap on 5/8" x 34" rebar  
 Set Blue Carsonite Post with loc. tag 1' NW  
 N7°E 29.52' to set nail & tag in W. side 26" R. Maple  
 S74°E 28.21' to set nail & tag in S. side 5" R. Maple  
 S23°W 17.27' to set nail & tag in SE side 7" R. Maple  
 S63°W 28.84' to set nail & tag in S. side 5" Fir

Signed by: Craig W. McVean Date: 5/26/2009  
 Surveyor's Michigan License No.: 39088