

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_  
 Clare  
 (County) Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey		T _____	R _____		
		T _____	R _____		
2. Property Controlling in Section	S 15	T 19N	R 6W	4	
	S 15	T 19N	R 6W	CNNW1/64	
3. Miscellaneous Property in Section	S _____	T _____	R _____		
	S _____	T _____	R _____		

Register of Deeds Stamp & File Number \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Oct. 2, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

4 - None.

CNNW 1/64 Corner Section 15 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

4 - NW 1/16 Corner Section 15.  
 Set a stamped 2" Aluminum Cap on a 5/8" x 34" rebar per Standard BLM procedure. East 97'± to centerline of N-S 2-track.

CNNW 1/64 Corner, Sec. 15 being the SE Corner of the N 1/2 of the NW 1/4 of the NW 1/4, Sect. 15 - Set stamped 2" Aluminum cap on a 5/8" x 34" rebar per Standard BLM procedure. East 124'± to centerline of N-S 2-track. Also found a 1/2" rebar of unknown origin is S84°30'W 31.39' from set 2" Aluminum Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4 - Stamped 2" Aluminum Cap on 5/8" x 34" rebar  
 N09°E 3.45' to set nail & tag in W. side 8" Red Pine  
 S73°E 31.07' to set nail & tag in N. side 8" Red Pine  
 S17°W 61.40' to set nail & tag in NW side 6" Red Pine  
 N80°W 78.19' to set nail & tag in N. side 7" Red Pine  
 Set Blue Carsonite Post with location tag 1' Southeast

CNNW 1/64 - Stamped 2" Aluminum Cap on a 5/8" x 34" rebar  
 S84°30'W 31.39' to found 1/2" rebar  
 S77°W 77.32' to set nail & tag in N side 14" Red Pine  
 S04°W 73.47' to set nail & tag in E side 5" White Pine  
 S25°E 120.80' to set nail & tag in NE side 4" W. Pine  
 N79°E 43.64' to set nail & tag in S. side 7" W. Oak

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 5/26/2009