

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. PA 1970  
**REMONUMENTATION**

For Corners In:  
 Clare \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 19N R 6W H3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on August 27, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    | ● |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

H3 – **1856** – GLO Resurvey - F. Coleman – Reestablished old  
 ¼ Sec. post  
 1) Y. Pine 14" N21°W 9 L.  
 2) W. Pine 20" S40°E 37 L.  
 - **1962** – Norton & Kobbins Notes.  
 Show ties to 2 Pine Stp. "Use this witness.  
 Add 1 ½' for edge of stp."  
 - **1975** – Rec. Survey – L. 2, p. 48 -  
 G. F. DeLaMater – Shows corner

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H3 – ¼ Corner common to Sec. 3 & 10 – Fd. 1 ½" I. D. iron pipe. Measured S40°E 23.4' to centerline of found remains of W. Pine Stp. that appears to be the stump referenced by the 1962 notes and could possibly be witness #2. Fits DeLaMater distance East closely. This position appears somewhat south of where GLO topographic ties to a NE-SW(N65°E-measure) bank bottom at 20.6 Ch (1305' +/- 10'- measure) to the east would cross. Searched to the north up to 40' feet but nothing else to find. Measured grid bearing and distance of S 89°51'38" E 2625.68' (2630.1'-GLO, 2626.49'-GFD) to 'I-3' and N 88°21'37" W 2598.11' (2616.9'-GLO) to 'G3'. Accepted 1 ½" iron pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H3 – Replaced 1 ½" x 2.3' long iron pipe with stamped 4" DNR Aluminum Cap on 1" x 36" galvanized iron pipe N48°E 12.54' to set nail and tag in S. side 16" Oak scribed 'XBT' S23°W 14.13' to set nail & tag in SE side 12" Oak scribed 'XBT' S30°E 21.39' to set nail & tag in W. side 4" Cherry N22°W 29.54' to set nail & tag in E. side 3" J. Pine Set Blue Carsonite Post 1' N.



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 10/20/2008