

SURVEY & REMONUMENTATION

APR 06 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE
(County)

Located In:

Corner Code ##

1. Public Land Survey

T	<u>19N</u>	R	<u>3W</u>	<u>A-7</u>
T	<u>19N</u>	R	<u>4W</u>	<u>M-7</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
2. Property Controlling in Section

S	_____	T	_____	_____
S	_____	T	_____	_____
3. Miscellaneous Property in Sec.

S	_____	T	_____	_____
S	_____	T	_____	_____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED
 E 10 A
 # 87-94
 94 DEC 29 AM 8:50

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M CARR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| 1856 CANNON, G.L.O. PG.407
POST
WIT.-(1)CEDAR 8" S33°W 30 LKS.
(2)CEDAR 11" N75°W 25 LKS. | 4-20-83 LAPHAM, L.C.R.C. #437
1" PIPE
WIT.-(5)N50°W 53.31' 12" CEDAR
(6)N20°E 37.77' 12" CEDAR
(7)S60°E 93.29' POWER POLE |
| 10-11-10 C.S.R. L.5-PG.90
WIT.(3)TAMARACK 4" N14°W 45 LKS.
(4)TAMARACK 4" S73°W 43 LKS. | 7-5-84 MCCLUNG (132)
1" PIPE
WIT.-(8)PLAT MONUMENT 33' SOUTH |
| 10-15-79 SEDGMAN, L.C.R.C. #348
1" PIPE
WIT.-(5)N50°W 53.31' 12" CEDAR
(6)N20°E 37.77' 12" CEDAR
(7)S60°E 93.29' POWER POLE | 6-2-89 LAPHAM, UNRECORDED SURVEY
SET IRON 49.0 FEET NORTH OF CORNER. |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND WITNESSES NO. 5,7,8. FOUND IRON 49.0 FEET NORTH. DUG HOLE IN NEW ASPHALT PAVEMENT. ROAD HAS BEEN RECENTLY FILLED ABOUT 2 FEET. FOUND 1 1/4"x18" PINCH PIPE AT 2.5 FEET. EXCAVATED TO 4' DEEP TO ORIGINAL SAND. FOUND NO FURTHER EVIDENCE. FOUND POSSIBLE WITNESS NO. 6 AT N20°E 32.68'.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul B. Lepkum
 Date 11-22-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.
 WITNESSES:
 N50°W 53.47' - NAIL & TAG IN 15" CEDAR (5)
 N20°E 32.68' - NAIL & TAG IN 12" CEDAR (6)
 S60°E 93.18' - NAIL & TAG IN POWER POLE (7)
 S75°W 131.11' - NAIL & TAG IN POWER POLE



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-22-94