

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 AD
 # 86-94
 94 DEC 29 AM 8:50

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in

CLARE
 (County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 19N R 3W | B-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	•												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEPT. 1856 CANNON POST. (1)W. PINE 14" N65°E 31 LKS (2)W. PINE 88" S39°E 25 LKS G.L.O. 10-11-10 (3)PINE 24" S62°E 80 LKS (4)PINE 24" S24°W 74 LKS C.S.R. 5-90

8-25-77 MCCLUNG, 5/8" ROD (132) 2-290
 1-18-78 MCCLUNG, PLAT OF DODGE CITY NO. 8. LIBER 15, PG. 41

9-5-79 LAPHAM, SUCKER ROD (5)N45°E 37.61' CORNERPOST (6)S45°W 48.40' 12" OAK (7)S10°W 43.47' 10" OAK (8)S10°E 40.50' 8" OAK L.C.R.C. #361-79

8-6-82 LAPHAM, SUCKER ROD (5,6,7,& 8)-ABOVE (132) 2-712
 7-26-83 LAPHAM, SUCKER ROD (5,6,7,& 8)-ABOVE (132) 2-781
 8-30-83 LAPHAM, SUCKER ROD (5& 6)-ABOVE (9)S40°E 8" OAK 40.50' (132) 2-793
 7-5-84 MCCLUNG, 5/8" BOLT (7)-ABOVE (10)12" RED OAK S45°W 47.7' (11)6" NOR. PINE N45°E 54.6' (132) 2-826

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8"x12" BOLT OVER 3/4"x24" PIPE. EXCAVATED TO 3 1/2 FEET. FOUND NO FURTHER EVIDENCE.
 FOUND WITNESS NO. 5 & 11.
 ALL TREES SOUTH OF ROAD IN R/W HAVE BEEN REMOVED, EXCEPT ONE 5" JACK PINE.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Lepkum
 Date 11-22-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C.
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX IN PVM'T.
 S45°E 95.30' - NAIL & TAG 20" W. OAK.
 N45°E 54.95' - NAIL & TAG 16" NORWAY PINE (11)
 S05°W 59.85' - MON.-724-725 LOT COR.
 S40°W 50.95' - NAIL & TAG 5" JACK PINE



Signed by

Mark R. Robison

Date 11-22-94

Surveyor's Michigan License No. 27458