

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 10 AD
 # 85-94
 94 DEC 29 AM 8:49

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in CLARE (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>T19N</u> R <u>3W</u>	<u>D-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1856, CANNON, POST, (1) Y. PINE 20" S70°W 42 LKS (2) Y. PINE 16" N85°E 39 LKS G.L.O.
 4-6-10 (3)OAK 4" N69 1/2°E 44 LKS (4)OAK 6" N79°W 87LKS C.S.R. 5-89
 11-6-73 LAPHAM, 1/2" RE-ROD, (5)NORTH 45.45' 5" TRIPLE OAK (6)SOUTH 24.03' POWER POLE (7)S50°W 73.20' 10" TWIN APPLE L.C.R.C. #121
 10-18-73 SEDGMAN, 1/2" RE-ROD, 5,6,& 7 (ABOVE) (132) 1-594
 1-7-74 URBANIAK, SEE L.C.R.C. #121 (132) 1-627
 11-3-75 SEDGMAN, FOUND 1/2" BAR, SEE L.C.R.C. #121 (132) 2-65
 9-27-84 LAPHAM, 1/2" CAPPED RE-ROD, (5)-ABOVE (8)SOUTH 31.97' POWER POLE (9)S45°W 71.92' 20" TWIN APPLE (10)N45°W 73.60' 10" RED PINE L.C.R.C.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2"x18" P.S. CAPPED IRON (9433) OVER 3/8" REBAR IN 3/4"x15" PIPE. FOUND NO FURTHER EVIDENCE.
 FOUND WITNESSES NO. 5, 8 & 9.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County
 Chairman Paul B. Spleen
 Date 11-22-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX IN @ ASPHALT PVM'T.
 N30°W 51.30' - NAIL & TAG IN 8" NORWAY PINE
 S60°W 58.90' - NAIL & TAG IN 6" NORWAY PINE
 NORTH 45.55' - NAIL & TAG IN TRIPLE 15" OAK (5)
 N25°E 54.90' - NAIL & TAG IN 15" OAK
 S45°W 71.80' - NAIL & TAG IN 20" APPLE (9)
 SOUTH 32.00' - NAIL & TAG IN POWER POLE (8)



Signed by Mark R. Robison Date 11-22-94
 Surveyor's Michigan License No. 27458