

CLARE COUNTY
REMONUMENTATION
COMMISSION

For corners in
APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 10 A D
84-94
94 DEC 29 AM 8:49

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

CLARE
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|------------|-----|
| 1. Public Land Survey | T 19N R 3W | E-7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- SEPT. 1856 CANNON, POST (1)W. PINE N53°E 30 LKS G.L.O. (2)W. PINE 14" S66°W 23 LKS G.L.O.
 - 4-6-10 (3)W. PINE 8" S34°E 35 LKS (4)W. PINE 24" S48°W 54 LKS C.S.R. 5-89
 - 6-19-36 A. JOHNSON (5)FENCE POST 7" N41°E 47 LKS. (6)POPLAR 8" N23 1/2°E 56 LKS. (7)OAK 16" NORTH 20' CSR 2-93
 - 11-6-73 LAPHAM, 3/8" IRON BAR (8)N50°E 55.65' 6" MAPLE (9)S70°E 74.23' 15" OAK (10)SOUTH 32.44' 8" CEDAR L.C.R.C. #121

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2"x18" L.L.S. CAPPED IRON 0.2' BELOW ASPHALT. AT 2 FEET DEPTH FOUND 5/8"x15' SUCKER ROD IN OLD ROAD BED. FOUND NO OTHER EVIDENCE.
FOUND WITNESSES: NOS. 8,9,& 10 AT APPROXIMATE DIST. TO TREES.
FOUND OLD FENCES RUNNING NORTH AND SOUTH FROM CORNERS.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul B. Lapham
Date 11-22-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX IN PVM'T.
N30°W, 43.65'- NAIL & TAG 10" CEDAR
S70°E 75.10'- NAIL & TAG 25" OAK (9)
SOUTH 32.2'- NAIL & TAG 15" CEDAR (10)
S50°W 54.25'- NAIL & TAG 15" CEDAR



Signed by Mark R. Robison Date 11-22-94
Surveyor's Michigan License No. 27458