

Survey & Remonumentation
 APR 06 1995
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 ED 10 AD
 # 83-94
 94 DEC 29 AM 8:49

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M CARR

For corners in CLARE (County) Located In: _____ Corner Code F-7

| | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>19N</u> R <u>3W</u> | <u>F-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|--|
| 1856 CANNON, G.L.O. PG.411 POST WIT.-HEMLOCK 11" N75°E 19 LKS. BEECH 13" S34°E 91 LKS. | 9-25-91 LAPHAM, (132) L.3-PG.301 FOUND SPIKE S60°W 84.40' 24" RED OAK SOUTH 36.10' FENCE CORNER S40°W 47.47' 14" POPLAR N40°E 57.30' POWER POLE |
| 4-6-10 A. JOHNSON, C.S.R. L.2-PG.1, L.5-PG.93 WIT.-BAMGILIAD 4" S47 1/2°E 42 LKS. | 5-4-92 LAPHAM, L.C.R.C. #670 FOUND SPIKE WIT.-S60°W 84.40' 24" RED OAK SOUTH 36.10' FENCE POST S40°W 47.47' 14" POPLAR N40°E 57.30' POWER POLE |
| 6-09-72 LAPHAM, BENTLEY SUBDIVISON, PLAT L.13-PG.24 | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SPIKE IN ASPHALT PAVEMENT, 49.0 FEET SOUTH OF CONCRETE MONUMENT AT S.W. CORNER, LOT 1, BENTLEY SUBDIVISION. RESURVEYED SOUTH 1/4 CORNER FROM BENTLEY SUBDIVISION, CORNER FELL 0.5 FEET SOUTH & 1 FOOT WEST OF SPIKE. EXCAVATED AT BOTH POINTS & FOUND NO FURTHER EVIDENCE. SET 1/4 CORNER FROM CONCRETE MONUMENT IN BENTLEY SUBDIVISION.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul A. Lapham
 Date 11-22-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

- WITNESSES:
 SOUTH 35.59' - NAIL & TAG - FENCE POST
 S60°W 82.90' - NAIL & TAG IN 24" RED OAK
 NORTH 49.50' - CONCRETE MONUMENT
 N40°E 58.50' - NAIL & TAG IN POWER POLE



Signed by Mark R. Robison

Date 11-22-94

Surveyor's Michigan License No. 27458