

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1990-0470

Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 12-03-1999 At 02:36 pm.
LAND CORNER 9.00
OR Liber 2 Page 108 - 108

For Corners in
Clare
(County)

Located In: Corner Code#:

1. Public Land Survey T. 19N R. 3W F-13
T. _____ R. _____
T. _____ R. _____

2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____

3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Instrument Liber Page
199900010470 OR 2 108

396-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13 1838 Nicholson
Set 1/4 Sec. Post

1971 Urbaniak,
Birch Hills Sportsmen Club Subd. #2. Rec. Plat (Erroneously used as common corner with F-1, T18N, R3W). All Standard Corners on the South line of T19N, R3W, were established in 1838. In 1856 the Closing Corners for T18N, R3W, were recovered in a GLO resurvey. The MSHD survey notes of 1933 state that the corners used in that survey are the T18N, R3W Closing Corners. The MSHD

right-of-way maps indicate that the Standard and Closing Corners are common (which they are not). All evidence of the original corners has been destroyed in highway construction. The preserved monumented corners have been used as both T19N & T18N, R3W, common corners in most subsequent surveys. Although not conclusive, farm fence lines south of this line tend to support the monuments as Closing

Corners. The 1856 resurvey of T18N, R3W, states that along with A-1 & M-1, B-1 & C-1 are also common with corresponding T19N, R3W, corners. In this remonumentation program, all lost Standard Section Corners have been established at the recorded G.L.O. distances from the Closing Corners and all lost Standard 1/4 Corners have been established at S. P.M. between section corners.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.

Found no evidence of corner. Set corner at S.P.M. on line with E-1 and G-1. Meas. 2634.38 both ways.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rod with Clare Co. Remon Cap marked P.S. #27458. Accepted as best available evidence of accepted method of re-establishment of the corner.

Witnesses:
S63°W, 115.84 N.E. Cor. Culv. Hdwl
S37°W, 99.84 N & T in Cor. F. Post
S12°E, 89.40 N & T in 18" R. Pine
N47°W, 69.74 N & T in 36" Oak
West 2.63 Closing Corner

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman Paul J. [Signature]

Date 12-08-98

Date 12-3-99