

CLARE COUNTY
REMONUMENTATION
COMMISSION
APR 06 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
E 10 A D
81-94
94 DEC 29 AM 8:48

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in CLARE (County) Located in: _____ Corner Code # _____

1. Public Land Survey	T <u>19N</u>	R <u>3W</u>	<u>1-7</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1856, CANNON, POST (1)CEDAR 16" S70°E 25 LKS (2)HEMLOCK 10" N05°W 20 LKS G.L.O.
 5-19-1989 (3)PINE 24" S49 1/2°W 62 LKS C.S.R. 94-5 (4)PINE 16" S48°E 61 LKS C.S.R. 5-95
 6-3-07 A.JOHNSON, (3 & 4)-ABOVE C.S.R. 5-87
 7-19-07 A.JOHNSON, (3)-ABOVE C.S.R. 120-4, (4)-ABOVE C.S.R. 4-112
 10-18-10 (3 & 4)-ABOVE C.S.R. 2-3
 10-18-71 LAPHAM, 1" PINCH IRON (5)N45°E 39.7' TELE. POLE (6)S45°E 35.7' SIGN POST (7)S45°W 83.5' POWER POLE. L.C.R.C. #21
 9-13-73 LAPHAM, SEE L.C.R.C. #21 (132) 1-595

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND OLD 1/2"x18" CAPPED IRON IN MON. BOX ± 2 FEET SOUTH OF CENTERLINE OF ASPHALT ROAD, IN CENTER OF ROAD NORTH-SOUTH. EXCAVATED TO 3 FEET. FOUND NO OTHER EVIDENCE.
 FOUND WITNESSES NO. 5 (MEAS. 39.9') & NO. 7 (MEAS. 83.85')

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul D. Leple
Date 11-27-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.

WITNESSES:
 N45°E, 39.90' - NAIL & TAG IN TELE. STUB. POLE. (5)
 S55°W, 83.85' - NAIL & TAG IN POWER POLE. (7)
 S10°E, 101.0' WEST END OF 8" CAST IRON DRAIN TILE.
 S80°W, 113.24' - NAIL & TAG IN 5" BIRCH.



Signed by Mark R. Robison

Date 11-22-94

Surveyor's Michigan License No. 27458