

NOV 18 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

RECORDED  
#203-97  
97 OCT 15 AM 10:49

or corners in

CLARE (County)	Located In:	Corner Code #
Public Land Survey	T 20N R 3W T 19N R 3W	K-13 K-1
1. Property Controlling in Section	T R T R	
2. Miscellaneous Property in Sec.	S T R S T R S T R	

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY

FRANKLIN  
HAMILTON

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1838 Nicholson GLO  
Hemlock 10" for Sec. Cor.  
4-25-73 Urbaniak (132) 1-486  
Fd. 3/4" bar  
Wit.-N30E 94.2 T.P.  
South 45.5 4" Cedar  
N45W 56.8 8" Tamarack
  - 1856 Cannon GLO  
Wit.-W. Pine 20" S42E 41  
Hemlock 13" S87W 45
  - 4-20-07 Johnson CSR 4-95 & CSR 5-73&74  
Wit.-Pine Stump 20" S42E 41  
Pine Stump 22" N54W 54
  - 7-24-73 Lapham LCRC#109  
Wit.-same as (132) 1-486
  - 11-06-73 Lapham LCRC#123  
Wit.-same as (132) 1-486

- Undated Sedgman (132) 1-671  
References LCRC#123
- 4-18-90 Wilcox LCRC#606  
Set 1/2" rebar w/ cap  
Wit.-N20W 63.07 14" Tamarack  
N55W 77.14 8" Cedar  
S45E 65.51 11" Tamarack  
South 47.60 6" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" x 18" rerod in monument box. Found no other material. Found one 1973 witness and all 1990 witnesses. Measured North 2683.62 (Recorded 2683.85) to K-12 per Sedgman survey. It appears 1973 witness South 45.5 to Cedar should be 47.5. Found C.I. to South 33.06 per Urbaniak survey. Arnold Lake Road underwent major reconstruction in the 1990's. Old Corners destroyed during construction were to be perpetuated by Wilcox, County Engineer.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman *Paul A. Lapham*  
Date 9-23-97

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" x 36" rerod with Clare County Remonumentation Cap marked P.S.#27458 in Monument Box. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
- N24E 94.2', N&T, top of P.P. Stub (OBT)
  - N20W 63.07', N&T, 14" Tamarack(OBT)
  - S45E 65.51', N&T, 11" Tamarack (OBT)
  - South 47.60', N&T, 6" Dead Cedar (OBT)
  - N55W 77.14', N&T, 9" Cedar(OBT)



Signed by *Mark R. Robison*  
Surveyor's Michigan License No. 27458

Date 10-01-97