

STATE OF MICHIGAN  
REMONUMENTATION

APR 06 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
E 10 A 0  
# 78-94  
94 DEC 29 AM 8:48

REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M CARR

For corners in \_\_\_\_\_ County, Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T19N R3W L-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856 CANNON, POST, (1) BEACH 13" S11°E 8 1/2 LKS, (2) BEACH 12" N11°W 11 LKS, G.L.O.
  - 5-6-07 A. JOHNSON, (3) PINE 44" N66 1/2 °E 41 LKS CSR 102-4
  - 6-3-07 A. JOHNSON, (3)-ABOVE, CSR 105-4
  - 1-3-92 J. MEYERS, FOUND 1/2" IRON, (4) NORTH 50.5' FENCE CORNER, (5) N 70°E 97.20' TELE. POLE (6) S10°W 22.60' FENCE POST (132) 3-332

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2"x18" P.S. CAPPED IRON OVER 18"x12" POINTED STONE WITH SEVERAL SMALLER STONES AROUND. EXCAVATED STONE AND ORIGINAL GROUND (CLAY) FOUND WITNESSES (4 & 6).

APPROVED LAND CORNER  
P.A. 345 of 1990  
Clare County

Chairman Paul B. Stephen  
Date 11-22-94

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN GRAVEL ROAD.  
WITNESSES:  
N70°E 99.65' CENTER OF TELE. RISER  
N65°W 70.40' 6" ELM (NAIL & TAG)  
NORTH 171.60' POWER POLE (NAIL & TAG)  
S70°E 48.20' 6" ELM. (NAIL & TAG)



Signed by Mark R. Robison

Date 11-22-94

Surveyor's Michigan License No. 27458