

REMOVAL
 DEC 1995
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 E 14 101 A 01
 # 115-95
 95 OCT -3 PM 2:51
 REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. GARR

For corners in CLARE Located in: _____ Corner Code # _____
 (County)

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>19N</u> | R | <u>4W</u> | <u>B-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling In Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK R. ROBISON, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7: 1/4 Corner common to Section 18 & 19
 1856 ADAIR, W. PINE 7 N5W-67, Y. PINE 14 N71E 136

MDOT, 1" T-IRON
 WITNESSES: N25E 23.57' 12" OAK
 S10W 22.64' 16" OAK
 N52W 29.70' 8" POPLAR

6-77 SEDGMAN, SAME AS 4-77 ABOVE (132) SURVEY
 7-77 SEDGMAN, SAME AS 4-77 ABOVE L.C.R.C.
 11-77 LAPHAM, SAME AS 4-77 ABOVE L.C.R.C.
 11-82 LAPHAM, SAME AS 4-77 ABOVE (132) SURVEY

1-77 LAPHAM, FOUND T-IRON
 4-77 LAPHAM, FOUND T-IRON
 WITNESSES: N25E 23.57' 12" OAK
 S10W 22.64' 16" OAK
 N52W 29.70' 8" POPLAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TWO WITNESSES AND CAPPED IRON 33.00 FEET NORTH OF CORNER, DID NOT FIND 1" T-IRON AT CORNER. EXCAVATED & DID NOT FIND ANY OTHER MATERIAL. RE-SET CORNER FROM C.I. 33.00 FEET NORTH, 16" OAK S10W 22.64' AND 8" POPLAR N52W 29.70'.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Lyle
 Date 10-26-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7: Corner common Sections 18 & 19
 SET 5/8"x36" RE-ROD WITH CLARE COUNTY MON. CAP. MARKED 1995, P.S. #27458.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
 N75W 29.70' - NAIL & TAG IN 13" POPLAR (OBT)
 N53E 97.28' - 27" R. OAK
 S5W 22.64' - NAIL & TAG IN W. OAK (OBT)
 S48E 54.72' - NAIL & TAG IN 16" R. OAK
 NORTH 33.00' - 1/2" CAPPED IRON



Signed by Mark R. Robison

Date 10-23-95

Surveyor's Michigan License No. 27458