

SURVEY & REMONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|--------------------------------------|---|---------------|
| 1. Public Land Survey | T. <u>19N</u> R. <u>4W</u> | <u>C-13</u> ✓ |
| | T. <u>18N</u> R. <u>4W</u> | <u>C-1</u> |
| | T. <u> </u> R. <u> </u> | <u> </u> |
| 2. Public Controlling in Section | S. <u> </u> T. <u> </u> R. <u> </u> | <u> </u> |
| | S. <u> </u> T. <u> </u> R. <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Section | S. <u> </u> T. <u> </u> R. <u> </u> | <u> </u> |
| | S. <u> </u> T. <u> </u> R. <u> </u> | <u> </u> |
| 4. Lot No. _____, Recorded Plat | | |
| 5. Private Claims | | |

200000009273
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 199 - 199

Instrument Liber Page
200000009273 OR 2 199

404-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 20, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T19N, R4W, & T18N, R4W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Nicholson, 1838
Pine 6" N33 1/2°E, 18 LINKS
Pine 6" N66°W, 40 LINKS

CSR
Arthur Johnson, 1912 CSR, Bk. 2. Pg. 22
Pine 36" S41 1/2°E, 56 LINKS
Oak 8" N24 1/2°E, 89 LINKS
C-13 to B-13 - 40.06

CSR, Bk. 6 Pg. 248
Pine 6" N33 1/2° E 18 LINKS

GLO, Cannon, 1856
W. Pine 30" S34°E, 60 LINKS
Hemlock 14" S84 1/2°W 90 LINKS

CSR, Bk. 6 Pg. 247
Pine 36" S 41 1/2°E, 56 LINKS
Oak 8" N24 1/2°E 89 LINKS
C-13 to B-13 - 40.00

Surveys None
Lapham, 1989 LCRC #594-89
Fd 1/2 Iron, 4 witnesses
See Section C

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Fd 1/2" Iron in Mon. Box. and 4 witnesses from LCRC #594-89. Measured 2643' C-13 to B-13, & 2632' C-13 - D-13. Accepted iron in Mon. Box as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rored with Clare County Remon Cap marked P.S. #27458 in Mon. Box.

Witnesses:
S70°E, 69.90' - N & T 42" Maple (OBT)
S85°W, 67.45' - N & T P. Pole (OBT)
N70°E, 75.83' - N & T 14" x 12" Maple (OBT)
West, 26.75' - Center of T. Rise (OBT)

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman *Mark R. Robison*
Date 8-30-00



Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 11-13-2000