

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 4W D-1
 T. 19N R. 4W D-13 ✓
 T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000009274
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-14-2000 At 11:04 am.
 LAND CORNER 9.00
 OR Liber 2 Page 200 - 200

Instrument Liber Page
 200000009274 OR 2 200

#405-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 20, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single common corner to T18N, R4W. & T19N, R4W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO CSR - None
- Nicholson, 1838 Private Files, Lapham, 1976
- B. Oak 18" N43°E, 20 LINKS Fd Iron
- Pine, 13" N43°W, 10 LINKS C-13 to D-13 = 2631.85
- D-13 to E-13 = 2628.60

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Sept
 Date 8-30-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Fd 3/4" iron in centerline East-West Road, 25 feet East (+-) of North-South Fence (fence warrants no location in position of corner). Measured C-1 to D-1, 2632 feet. Measured D-1 to E-1, 2629 feet. Excavated to 3 feet. Found nothing further. Iron used in Lapham 1976 survey with current distances matching 1976 distances. Accepted 3/4" Iron as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare County Remon Cap marked P.S. #27458.

Witnesses:

- N48°W, 47.69' - N & T 22" B. Oak
- S63°W, 62.75' - N & T 12" x 12" x 12" B. Oak
- North, 31.83' - N & T 24" B. Oak
- N33°E, 59.73' - N & T 22" B. Oak with Twin Top



Signed by Mark R. Robison

Date 11-13-2000

Surveyor's Michigan License No. 27458