

CLARE County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 # 266-98  
 98 NOV 18 AM 9:54  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. BAULAY

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #	
1. Public Land Survey	T20N R04W	E-13	
	T19N R 04W	<u>E-1</u>	
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on June 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T20N, R04W  
 E-13 and T19N, R04W E-1

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |  |
|--|--|
| E-13: 1838 Nicholson Set Post Cor Sec 32-33<br>Wit-Aspen 9 N84E 37 & Oak 10 N59W 50                        | 11-06-46 F. McClung 2-36<br>NE Cor AIRPORT FOREST SUBD. NO. 2  |
| Subdivision T19N, R4W<br>Wit-B. Oak 8 S66 1/2E 43<br>S. Pine 5 S50 1/4W 33                                 | 9-22-47 F. McClung 2-46<br>SW Cor PLAT OF NORTHWOOD HILLS  |
| circa 1900 Unknown CSR 5-220<br>Wit-B. Oak 6 S61E 10<br>W. Oak 4 S51W 33                                   | 10-30-47 F. McClung 2-49<br>SW Cor AIRPORT FOREST SUBD. NO. 3  |
| circa 1900 Unknown CSR 5-284/5-285<br>Oak stake 3<br>Wit-B. Oak 8 S89E 30 1/2<br>S. Pine 8 N52 1/2W 68 1/2 | 5-28-93 Porter<br>Fd 1 1/2" Pipe in Conc Mon<br>Wit-West 23.95 18" Oak<br>SWW 56.36 14" Pine<br>SW 49.11 12" Pine<br>NEE 38.0 P.P. |

**SURVEY &  
 REMONUMENTATION**  
  
 NOV 25 1998  
  
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 E-13: Found 1 1/4" pipe in concrete. Found all 1993 witnesses. Excavated but found no other material.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 E-13: Set 5/8" x 36" rered with Clare Co. Remon. Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 West 23.95', nail & tag, 22" Oak (OBT)  
 S70W 56.36', nail & tag, 17" R. Pine  
 S47W 49.11', nail & tag, 16" R. Pine  
 N52E 38.00', nail & tag, P.P.



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul S. Apple  
 Date 9-22-98

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11-16-98