

**SURVEY & REMONUMENTATION**

**JAN 23 2001**

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in <u>Clare</u> (County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>18N</u> R. <u>4W</u>	<u>E-1</u>
	T. <u>19N</u> R. <u>4W</u>	<u>E-13</u>
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat	_____	
5. Private Claims	_____	

200000009275  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 11-14-2000 At 11:04 am.  
 LAND CORNER 9.00  
 OR Liber 2 Page 201 - 201

Instrument Liber Page  
 200000009275 OR 2 201

# 406-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 20, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

This is a single corner common to T18N, R4W, & T19N, R4W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Nicholson, 1838 Maple 8" N71°E, 42 LINKS	LCRC, Batzer, 1972 #51-72 Found 1" Pipe per MSHD, 3 witnesses
B. Oak 26" N28°W, 09 LINKS	Survey, Robison, 1994 not recorded Same LCRC #51-72 plus 1 additional witness

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul S. [Signature]  
 Date 8-30-00

GLO  
Cannon, 1856  
Y. Pine 10" S30°W, 50 LINKS  
W. Oak 5" S35°E, 25 LINKS

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No GLO evidence found. Found 1 1/2" x 14" pipe and 4 OBT'S from Batzer/Robison. No record found from MSHD files. No evidence of other corners found. Old fence North falls 30' West of pipe (fence accords no bearing in this corner) measured E-1 to D-1 as 2629, measured E-1 to F-1, 2643. Accepted found pipe as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458.  
 Witnesses:  
 N55°W, 52.15' - N & T in 10" x 10" x 10" Maple (OBT)  
 N34°E, 22.94' - N & T in 12" Maple (OBT)  
 S35°E, 56.88' - N & T in Power Pole (OBT)  
 S23°W, 75.16' - N & T in 15" W. Pine (OBT)



Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11-13-2000