

FEB 18 1994

CLARE COUNTY REMONUMENTATION PROGRAM

RECEIVED

1993 DEC 20 PM 1:49

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
CLARE COUNTY
DONNA M. CARR

For corners in

CLARE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 19N R 4W F-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, MARK R. ROBISON in a field survey on NOVEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1857 G.E. ADAIR, W. PINE 20" N 80-1/2°W, 11 LKS P.382
 - W. PINE 20" S 55°E, 24 LKS
 - 10-2-72 LAPHAM, FOUND IRON LCRC 52-72
 - 7-12-74 SEDGMAN, (132) 1-748
 - 10-15-79 SEDGMAN, FOUND 1/2" BAR LCRC 346-79

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1-1/2" x 18" PIN WITH 3" DIAMETER TOP (VERY OLD & RUSTED).
 - EXCAVATED TO 3', DID NOT FIND ADDITIONAL EVIDENCE. LEFT PIN IN BOTTOM OF HOLE
 - FOUND RECORDED WITNESSES:
 - N 30°E, 77.03' - NAIL & TAG IN 16" OAK
 - S 20°E, 65.18' - NAIL & TAG IN 18" OAK

MEASURED 2674.98' (RECORDED 2675.0' IN (132) 1-748) NORTH TO INTERIOR 1/4 CORNER OF SECTION 28

This Corner established in Clare County Remonumentation Program. See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 - N 30°E, 77.00' - 18" OAK
 - S 10°E, 65.24' - 20" OAK
 - S 70°E, 99.40' - POWER POLE
 - N 75°W, 167.30' - POWER POLE

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458