

**SURVEY & REMONUMENTATION**

**JAN 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in  
Clare

200000009276  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 11-14-2000 At 11:04 am.  
 LAND CORNER 9.00  
 OR Liber 2 Page 202 - 202

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>18N</u> R. <u>4W</u>	<u>F-1</u>
	T. <u>19N</u> R. <u>4W</u>	<u>F-13</u> ✓
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Instrument Liber Page  
 200000009276 OR 2 202

#407-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 4, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

This is a single corner common to T18N, R4W, & T19N, R4W.

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO  
 Nicholson, 1838  
 Aspen 8" N40°E, 07 LINKS  
 B. Oak 6" N30°W, 10 LINKS

C.S.R., Unknown, Bk. 6 Pg. 249  
 Blk. Oak 18" N23°E, 13 LINKS  
 Pine Stump 18" N70°W, 15 LINKS

LCRC, Lapham, 1974 #170-74  
 Found well point, 3 witnesses

LCRC, Sedgman, 1977 #298-77  
 Found concrete monument, same  
 3 witnesses as LCRC #170-74

Plat of Forest Highlands, Batzer, 1975, L. 15. Pg.9-12  
 Concrete monument for corner

Survey, Batzer, 1975 L1. Pg. 935  
 Same as LCRC #170-74

Survey, Batzer, 1975, L1. Pg. 937  
 Same LCRC #170-74

Survey, Sedgman, 1977, L2. Pg. 331  
 Same as LCRC #298-77

**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County  
 Chairman Paul B. Lopp  
 Date 8-30-00

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.**  
 No GLO or CSR evidence found. Found concrete monument with 1 1/2" x 36" well point beside it. Excavated to 3' nothing else found and no evidence of other corners found. Remains of all 3 witnesses found. Accepted concrete monument as best available evidence of accepted position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 36" rered with Clare County Remon Cap marked P.S. #27458.  
 Witnesses:  
 N39°W, 14.85' - N & T in 10" Red Oak  
 N58°E, 37.45' - N & T in 16" Red Oak  
 S30°W, 18.30' - N & T in 12" x 12" Red Oak  
 S70°E, 17.23' - N & T in 7" Maple



Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11-13-2000