

**SURVEY & REMONUMENTATION**

FEB 18 1994

COMMISSION

**CLARE COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED  
 1993 DEC 20 PM 1:48

REGISTER OF DEEDS  
 CLARE COUNTY  
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
	T <u>19N</u> R <u>4W</u>	<u>G-7</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1856 G.E. ADAIR, W. PINE 18" S 75°W, 35 LKS P. 358  
 CHERRY 5" N 46-1/2°E, 43 LKS  
 4-15-00 UNIDENTIFIED, CHERRY 5" N 46-1/2°E 43 LKS CSR 5-238  
 6-4-36 A. JOHNSON, MAPLE 6" N 53°30'E CSR 2-95  
 CHERRY 5" N 46-1/2°E 43 LKS  
 STAKE, CENTER OF HIGHWAY  
 4-12-74 M. McCLUNG, COMMENTS re: CORNER LOCATION (132) 1-913  
 11-29-89 LAPHAM, LCRC 602-89

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" x 6" RE-BAR, VERY BADLY RUSTED. FOUND NO OTHER EVIDENCE  
 FOUND RECORDED WITNESS:  
 S 40°W, 69.6' - 18" OAK

This Corner established in Clare County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 5/8" X 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.  
 N 05°E, 71.25' - 5" WHITE OAK  
 N 55°W, 84.50' - CORNER FENCE POST  
 S 35°W, 70.35' - 30" OAK  
 S 25°E, 38.95' - 6" POPLAR



Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11/24/93