

SURVEY & REMONUMENTATION

CLARE COUNTY REMONUMENTATION PROGRAM

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 20 PM 1:48

For corners **COMMISSION**

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>CLARE</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>19N</u> R <u>4W</u> | <u>G-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1856 G.E. ADAIR, POST - W. OAK 4" N 19°W, 16 LKS 370
 W. OAK 5" S 81-3/4°E, 28 LKS
 9-7-13 A. JOHNSON, PINE 24" S 53°E, 44 LKS CSR 1-31
 12-26-72 M. McCLUNG, FOUND IRON LCRC 79-72
 7-24-73 LAPHAM LCRC 79-72
 11-29-76 SEDGMAN LCRC 258-76

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" x 18" RE-ROD OVER 5/8" x 15" BAR. EXCAVATED TO 36" DEPTH, FOUND NO OTHER EVIDENCE.
 FOUND RECORDED WITNESSES:
 N 20°W, 71.23' - POWER POLE
 N 50°E, 57.22' - POWER POLE
 S 10°E, 102.25' - POWER POLE

This Corner established in Clare County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 5/8" x 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 N 20°W, 71.21' - POWER POLE
 N 50°E, 57.33' - POWER POLE
 S 10°E, 102.38' - POWER POLE
 S 25°W, 40.50' - U.G. CABLE MARKER (3" PIPE)
 S 60°E, 53.29' - N.W. COR. BLOCK BLDG.



Signed by Mark R. Robison

Date 11/24/93

Surveyor's Michigan License No. 27458