

CLARE COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
E O I O A D  
# 48-93  
1993 DEC 20 PM 1:49

REGISTER OF DEEDS  
CLARE COUNTY  
DONNA M. CARR

For corners in

CLARE (County)	Located In:	Corner Code #
1. Public Land Survey	T 19N R 4W	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY &  
REMONUMENTATION

OCT 08 1999

SECTION Needs Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
1857 G.E. ADAIR, B. OAK 22" N 34-1/2"W, 55 LKS P. 369  
W. PINE 16" S 50°E, 34-1/2 LKS  
10-17-51 F. McCLUNG, SUPERVISOR'S PLAT OF ALLEN-DALE 3-18  
8-20-75 LAPHAM, 1/2" BOLT LCRC 211-75  
2-19-80 LAPHAM, ASSESSOR'S PLAT OF 3rd ADDITION TO ALLEN-DALE 16-24/25

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
DID NOT FIND ANY RECORDED WITNESSES. SURVEYED FROM MONUMENT AT S.W. CORNER OF LOT 25, ASSESSOR'S PLAT OF THE THIRD ADDITION TO ALLEN-DALE, BACK TO THE S.W. CORNER OF SECTION 27. SET SPIKE AND P.S. DISK AT CORNER LOCATION IN ASPHALT OVER CONCRETE PAVEMENT. SET REFERENCE POINT (1/2" x 18" RE-ROD - P.S. CAPPED) N 89°06'36"W, 20.00' AND S 89°06'36"E, 20.00' FROM CORNER.

This Corner established in Clare County Remonumentation Program.  
See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET SPIKE AND P.S. DISK AT CORNER LOCATION IN ASPHALT OVER CONCRETE PAVEMENT.  
N 67°13'26"E, 82.21' - CONC. MONUMENT  
N 89°06'36"W, 20.00' - 1/2" x 18" RE-ROD, REF. POINT  
S 89°06'36"E, 20.00' - 1/2" x 18" RE-ROD, REF. POINT  
S 30°E, 69.00' - 15" NORWAY PINE  
S 45°W, 68.80' - 12" OAK



Signed by Mark Robison

Date 11/24/93

Surveyor's Michigan License No. 27458

LIBER 1 PAGE 1161