

RECEIVED
 E 17 17
 #191-96
 96 DEC 23 AM 11:59

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE Located In: Corner Code #
 (County)

1. Public Land Survey T 19NR 4W H-7
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on AUGUST, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 ADAIR 8-23-74 McCLUNG, L.C.R.C. #196
 WIT.- SET POST WIT.- FOUND MON. BOX.
 Y. PINE 11" N33°W 10 1/2 LKS.
 Y. PINE 6" S75 1/4°E 17 LKS. 1-11-95 GRAY
 WIT.- FOUND 5/8" ROD IN E TOWNLINER LAKE ROAD
 UNDATED UNKNOWN, C.S.R. L.5, PG. 238 OFF EXTENSION OF HWY.
 WIT.-SAP. PINE 12" S. 14 LINKS. R/W FENCE NORTH & SOUTH.
 H-7 TO G-7 = 39.36'
 H-7 TO I-7 = 39.36'

MSHD 254' AZ 47.76' TOP S.W. COR. CONC. BRIDGE RAIL
 MEAS. 2633.10' FEET TO I-7 293' AZ 48.19' TOP N.W. COR. CONC. BRIDGE RAIL
 60' AZ 29.69' N&C IN TOP OF GUARD POST
 127' AZ 30.75' N&C IN TOP OF GUARD POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MONUMENT BOX BUT NO IRON, IN NEW PAVEMENT, WITNESSES FIT A POINT ONE FOOT WEST OF MONUMENT BOX. THE CLARE COUNTY ROAD COMMISSION ENGINEER STATED THAT BOX HAD BEEN REMOVED AND REPLACED IN 1995 SUMMER PAVING PROJECT. WE ESTABLISHED CORNER IN CONFORMANCE TO WITNESSES AND RE-SET MONUMENT BOX. MEASURED 2633.58' (MDOT 2633.10') EAST TO I-7. MEASURED 2643.75' WEST TO G-7.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Sept
 Date 8-29-96

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN MONUMENT BOX.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
 S74°W, 47.76' - TOP S.W. COR. CONC. BRIDGE RAIL (OBT).
 N77°W, 48.19' - TOP N.W. COR. CONC. BRIDGE RAIL (OBT).
 N60°E, 29.69' - NAIL & CAP IN TOP OF GUARD POST (OBT).
 S53°E, 30.75' - NAIL & CAP IN TOP OF GUARD POST (OBT).



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 12-20-96