

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 4W H-1
T. 19N R. 4W H-13 ✓
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000009278
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 204 - 204

200000009278
PAUL B LAPHAM & ASSOC INC
PO BOX 33
CLARE, MI 48617

#409-00

Instrument Liber Page
200000009278 OR 2 204

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 9, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single corner common to T18N, R4W, & T19N, R4W.

A. Description of original monument and accessories and/or subsequent restoration:

GLO
Nicholson, 1838
B. Oak 22" N2°W, 50 LINKS
B. Oak 8" N66°W, 54 LINKS

Survey, Lapham, 1977, L2. Pg. 218
Same as LCRC #312-77

Survey, Robison, 1996, L621. Pg. 356
Same as LCRC #312-77

MDSH, card, Slattery 1958
1/2" pipe in concrete by Moore
4" Oak N70°E, 6.38
5" Birch N89°E, 17.45
4" Maple S30°E, 6.95

Survey, Sedgman, 1978, L2. Pg. 359
Same as LCRC #312-77
H-13 to I-13 = 2634.74

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

LCRC, Lapham, 1977, #312-77
Found concrete monument, same 3 witnesses
as MDSH card

Survey, Robison, 1994, L3. Pg. 448
Same as LCRC #312-77

Chairman *Mark R. Robison*
Date 8-30-00


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

No GLO evidence found. Found concrete monument and remains of maple stump of 1958 witness SE. Measured distance H-13 to I-13 as 2634.74. Accepted found concrete monument as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare County Reimon Cap marked P.S. #27458.

Witnesses:
N66°W, 16.75' - N & T in 14" x 12" Red Oak
N84°E, 33.33' - N & T in 18" Red Oak
N35°E, 34.17' - N & T in 11" Red Oak
N3°E, 34.00' - N & T in 7" Red Oak



Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 11-13-2000