

RECEIVED
 E 17 17
 #183-96
 96 DEC 23 AM 11:59

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

For corners in

<u>CLARE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 19N R 4W	L-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1857 ADAIR WIT.-ASPEN 8" N56°E 18 LKS. ASPEN 6" S31 1/2° W 18 LKS.	7-19-74 LAPHAM, L.C.R.C. #151 WIT.- SAME AS 6-25-74
UNDATED UNKNOWN, C.S.R. L.5, PG. 229 WIT.-NORWAY 13" S16°E 25 LKS. NORWAY 12" N24°E 85 LKS. L-7 TO K-7 & 39.75	7-27-74 McCLUNG, (132) L.1, PG. 924 WIT.-1" PIPE WITH CAP. N45°E, 47.45' - 30" W. PINE. N02°W, 36.10' - 30" B. OAK. N50°W, 87.60' - 13" W. OAK.
6-25-74 LAPHAM, (132) L.1, PG. 737 WIT.-FOUND 1" CAPPED PIPE. N10°W, 37.24' - 33" OAK. N50°E, 48.49' - 30" PINE. S45°E, 24.71' - GUARD POST.	08-01-74 McCLUNG, L.C.R.C. #195 WIT.- SET ON LINE & PRORATED DISTANCE SAME WITNESSES AS 7-27-74

10-18-76 SEDGMAN, (132) L.2, PG. 179
WIT.-FOUND 1" PIPE WITH R.L.S. CAP.
SAME AS 6-25-74 WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 18" SUCKER ROD (UPSIDE DOWN) WITH CAP INSIDE. FOUND 1974 WITNESSES AS SHOWN BELOW.
 SEARCHED FOR CORNER EVIDENCE AT S.P.M. BETWEEN K-7 & M-7 BUT DID NOT FIND FURTHER EVIDENCE.
 CORNER FALLS IN DEEP FILL SECTION. NO EVIDENCE OF OCCUPATION NORTH OR SOUTH.

APPROVED LAND CORNER
 P.A. 345 of 1980
 Clare County

Chairman Paul S. Sept
 Date 11-14-96

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"x36' RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
 N16°W, 37.29' - NAIL & TAG IN 40" R. OAK (OBT).
 N42°E, 48.49' - NAIL & TAG IN 32" R. PINE (OBT).
 N54°W, 81.96' - NAIL & TAG IN 18" R. OAK.
 S15°E, 71.84' - NAIL & TAG IN 23" R. OAK.



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 12-20-96