

SURVEY & REMONUMENTATION

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

200000009283
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-14-2000 At 11:04 am.
 LAND CORNER 9.00
 OR Liber 2 Page 209 - 209

(County) Located In: Corner Code#:

1. Public Land Survey T. 20N R. 3W C-7
 T. _____ R. _____
 T. _____ R. _____

2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____

3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Instrument Liber Page
 200000009283 OR 2 209

414-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 10, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Surveys
 Adair, 1856 None
 Tamarack 4", N45 1/2°E, 13 LINKS
 Spruce 4" S68°W, 15 LINKS LCRC'S
 None

C.S.R.
 None

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul H. Lopp
 Date 5-10-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found intersection of ancient fence lines in marsh. Measures C-7 to E-7 5285.12 (G.L.O. = 80.00). Measures C-7 to A-7 5413.88 (G.L.O. = 81.15). G.L.O. call to West edge marsh = 3.15 chains = 207.9 feet. Measures to West edge marsh = 210 feet. Accepted fence corner as best available evidence of accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458 at intersection of fences.

Witnesses:

South 160' - Edge of marsh
 West 210' - Edge of marsh
 S18°W, 26.36' - N & T East side of Fence Post
 N60°E, 7.61' - N & T West side of 3" Larch
 S10°E, 249.24' - N & T West side of 24" R. Pine



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-13-2000