

JAN 23 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare
 (County)

1. Public Land Survey	T. <u>20N</u> R. <u>3W</u>	<u>D-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat	_____	_____
5. Private Claims	_____	_____

200000009284
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-14-2000 At 11:04 am.
 LAND CORNER 9.00
 OR Liber 2 Page 210 - 210

Instrument Liber Page
 200000009284 OR 2 210

#415-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 10, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	Surveys
Adair, 1856	None
Hemlock 12" N43°W, 7 LINKS	
Hemlock 9" S57°E, 29 LINKS	LCRC
	None
C.S.R.	
None	

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Lytle
 Date 5-10-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No evidence found. Set by single proportionate measure. Corner falls 8' North of East-West fence. Adjoiners stated fences for live stock only. Corner set on straight line between C-7 and E-7 at a distance of 2642.56.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458. Accepted established corner as best available evidence of accepted position of the corner.

Witnesses:
 S68°E, 26.10' - N & T Southwesterly side Fence Post
 S23°E, 9.30' - N & T West side Fence Post
 S71°W, 18.65' - N & T Southeasterly side of Fence Post
 S83°W, 37.65' - N & T South side of Fence Post



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-13-2000