

**SURVEY &  
REMONUMENTATION**

**JAN 23 2001**

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 3W E-7  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

200000009285  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-14-2000 At 11:04 am.  
LAND CORNER 9.00  
OR Liber 2 Page 211 - 211

Instrument Liber Page  
200000009285 OR 2 211

#416-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
Adair, 1856  
Beech 13" N28°E, 24 LINKS  
Maple 8" S64°W, 31 LINKS

Surveys  
Lapham, 1979 L 2, Pg. 459. Found 3 witnesses  
Robison, 1994 Unrecorded  
Henning, 1963 Section 16, Unrecorded  
Sedgman, 1980 Field Notes, Unrecorded

C.S.R.  
None

L.C.R.C  
Lapham, 1979, #364-79

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" x 12" Pipe. Found O.B.T. from Henning 1963 and Lapham L 2, Pg. 459 and LCRC #364-79. Accepted found pipe as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458 at position of 3/4" pipe.

Witnesses:  
N38°E, 117.5' - N & T 24" R. Oak (OBT)  
West, 20.67' - N & T 6" Cherry  
N18°W, 102.18' - N & T 18" R. Oak  
S49°W, 26.75' - N & T 7" Maple



**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Lapham  
Date 5-10-00

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-13-2000