

**SURVEY &
REMONUMENTATION**

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

SECTION

For Corners in
Clare

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>20N</u> R. <u>3W</u> | <u>F-7</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

200000009289
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 215 - 215

Instrument Liber Page
200000009289 OR 2 215

#420-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O.
Adair, 1856
B. Oak 12" N4°W, 24 LINKS
Maple 7" S49 ½°E, 24 LINKS
- C.S.R.
Johnson, 1916
Bk. 2 Pg. 40
W. Pine 36" N65°W, 83 LINKS

- Surveys
Henning, 1963
Set at S.P.M. E-7 to H-7 per C.S.R.
- LCRC'S
Gray, 1996 #797-96
- Notes
Sedgman, 1980

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul S. Taylor
Date 5-20-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" Re-rod. Witnesses from LCRC #797-96. Measure 2662.25 F-7 to G-7, (Henning, 2664 feet). (Sedgman, 2662.15). Accepted found rered as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458.
Witnesses:
N39°W, 9.72' - N & T 10" Maple
N78°E, 29.6' - N & T 16" Oak
West 1.23' - N & T 4" Oak
South 0.28' - Fence Post



Signed by Mark Robison
Surveyor's Michigan License No. 27458

Date 11-13-2000