

**SURVEY &
REMONUMENTATION**

MAR 24 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

For Corners in
Clare
(County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>3W</u>	<u>F-9</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900007853
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 09-20-1999 At 11:15 am.
LAND CORNER 9.00
OR Liber 2 Page 17 - 17

Instrument Liber Page
199900007853 OR 2 17

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on July 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Adair
Set 1/4 Sec. Post
Beech 12 N64E 34
W. Pine 4 S18W 12

1916 Johnson, CSR 2-40
W. Pine 20 N46-30E 37
W. Pine 14 S3-30W 12 Gov't
Meas. West 40.34
Meas. East 40.68

1996 Gray LCRC #801
Fd RR bolt in centerline gravel
road - reset with 1/2 x 18" bar & cap
S48E 37.37 12" R. Maple
S10W 57.42 P.P.
S24W 21.38 30" W. Oak
N22E 30.09 4" W. Oak
North 33.00 1/2" bar w/cap

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman *Paul S. Papp*
Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.

Found 1/2" x 18" rebar & cap and 1" x 6" bolt at corner. Found all 1996 witnesses. Meas. West 2644.29 to E-9. Meas. East 2644.98 to G-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rod with Clare Co. Remon Cap marked P.S. #27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:

N18°W 54.13 Top Cen 4" sq. Conc/steel gate post
S45°E 37.41 N & T in 12" Maple (OBT)
S27°W 21.36 N & T in 30" W. Oak (OBT)
S08°W 57.45 N & T in P.P. (OBT)



Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 9-15-99