

**SURVEY &
REMONUMENTATION**

JAN 23 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

For Corners in
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 3W G-7
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

200000009288
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 214 - 214

Instrument Liber Page
200000009288 OR 2 214

#419-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
Adair, 1856
W. Pine 23" N51°E, 28 LINKS
W. Pine 15" S31°W, 2 LINKS

Surveys
Henning, 1963, Unrecorded
Set S.P.M. E-7 to H-7 per C.S.R.
McClung, 1972, L1. Pg. 179

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County
Chairman Paul B. Sept
Date 5-10-00

C.S.R.
Johnson, 1916
Bk. 2 Pg. 40 & Bk. 2 Pg. 42
Gov't Witness

LCRC
McClung, 1972 #38-72 McClung, 1972 #38-72

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 24" Re-rod. Found O.B.T.'S from LCRC #38-72. Measured 2662.25 G-7 to F-7, (Henning 2664 feet) (Sedgman, 2662.15'). Accepted found rered as best available evidence of the accepted position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458.

Witnesses:
East, 13.64' - N & T 14" Maple Clump
West, 1.05' - N & T Fence Post
N23°W, 24.3' - N & T 10" x 14" x 10" Triple Red Oak
N25°E, 46.5' - N & T 12" Maple



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-13-2000