

**SURVEY &  
REMONUMENTATION**

**JAN 23 2001 LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**SECTION Clare County Remonumentation**

For Corners in  
Clare  
(County)

Located In: Corner Code#:

1. Public Land Survey T. 20N R. 3W H-7  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

200000009287  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-14-2000 At 11:04 am.  
LAND CORNER 9.00  
OR Liber 2 Page 213 - 213

Instrument Liber Page  
200000009287 OR 2 213

# 418-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. Surveys  
Nicholson, 1839 McClung, 1990 L1, Pg. 263  
G.L.O., Re-survey McClung, 1972 L1, Pg. 179  
Adair, 1856 Sedgman, 1976 L2, Pg. 250  
White Pine 18" N60 1/2 E, 25 LINKS Meyers, 1980 Unrecorded  
White Pine 17" S51°W, 30 LINKS Robison, 1991 Unrecorded  
Henning, 1963 Unrecorded (Gov't)
- C.S.R.  
Johnson, 1916, Bk. 2 Pg. 42 (Gov't)

- LCRC'S  
McClung, 1972 #38-72  
Sedgman, 1978 #318-78

**APPROVED LAND CORNER**  
**P.A. 345 of 1990**  
**Clare County**  
Chairman Paul A. Loph  
Date 5-10-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 24" re-rod and witnesses from #318-78 and #38-72 and Sedgman, Meyers, & Robison survey. Accepted found iron as best available evidence of the accepted position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S. #27458.

Witnesses:

- N60°E, 34.81' - N & T 13" x 10" Red Oak (OBT)  
East, 39.50' - N & T 12" Red Oak (OBT)  
N30°W, 20.40' - Found maple stump with nail (OBT)  
N20°E, 10.35' - N & T 18" x 15" Red Oak  
N33°W, 22.31' - N & T 8" Maple



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-13-2000