

**SURVEY &
REMONUMENTATION**

JAN 23 2001

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

SECTION

For Corners in

<u>Clare</u> (County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>3W</u>	<u>I-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

200000009286
Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-14-2000 At 11:04 am.
LAND CORNER 9.00
OR Liber 2 Page 212 - 212

Instrument Liber Page
200000009286 OR 2 212

417-00

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 6, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Nicholson, 1838	C.S.R. Johnson, 1916, Bk. 2, Pg. 42	Henning, 1963 Unrec. Survey
G.L.O. Re-survey Adair, 1856	Surveys Ostling (DNR) 1973, Unrecorded (used Henning corner)	LCRC McClung, 1972, #38-72
Beech 7" N76°W, 17 LINKS	Robison, 1991, Unrecorded	
White Pine 19" S55 ½ E, 8 LINKS	McClung, 1972 LI, Pg. 179	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 30" Pipe and witness from LCRC #38-72 and one witness from Henning survey. Excavated 1' found nothing further. Accepted found pipe as best available evidence of the accepted position of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare County Remon Cap marked P.S #27458.

Witnesses:
N50°E, 45.6' - N & T 12" Maple (OBT)
N28°E, 30.9' - N & T 14" x 10" Maple
N24°E, 12.7' - N & T 5" Red Oak
S10°W, 19.85' - N & T 8" Maple
S80°W, 55.2' - 20" B. Oak (OBT)

**APPROVED LAND CORNER
P.A. 345 of 1990
Clare County**

Chairman Paul J. [Signature]
Date 5-10-00



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 11-13-2000