

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 20 N. R. 3 W


Clare COUNTY

DESCRIPTION OF CORNER 1/4 corner on N. Side Section 6, on 2nd correction line

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 22, 1966

WITNESSES TO CORNER.....



5" J. Pine N 15 E 8.6'

7" Aspen S 8 E 2.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between respective section corners of Section 6. This corner was not set in U.S. survey, and apparently never restored in any subsequent survey. A $1\frac{1}{2}$ " pipe is about 2 chs east and 20 links north, which we believe to be a ground water checking station.

SURVEYOR'S SEAL

SIGNED Kenneth J. Osting DATE June 22, 1966
REGISTERED LAND SURVEYOR #10088