

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

True

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> ^{N.} <input checked="" type="radio"/> R. <u>3</u> ^{W.} <input checked="" type="radio"/>	<u>K-6; J-6; J-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ ^{N.} S. _____ ^{E.} ^{W.} _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. _____ ^{E.} ^{W.} _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 24, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-6 Found 2" pipe at corner, apparently used by other local surveys.
- J-6 Set at calculated intersection of true 1/4 lines, per standard survey procedures.
- J-7 Set by proportionate measurement between section corners. No U.S. evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6	J-6	J-7
Set DNR Mon. & red top post	Set 2 1/2' of 1" pipe; 4" below road surface; red top post south - 6'	DNR Mon. & red top post
11" Bl. Oak N23E 17.3'	5" Maple N08W 24.2'	6" R. Oak N55E 15.0'
14" R.P. Stp. S40E 6.45'	19" Bl. Oak N75E 100.4'	10" R. Oak S43E 24.9'
7" W. Oak S57W 43.0' (in clump of 4)	Falls 9' south of road 6	

SIGNED BY *Kenneth J. Ostling* DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
 APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)