

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> ^{N.} _● , R. <u>3</u> ^{W.} _●	<u>K-7; K-8; K-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 23, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-7 Set corner by double proportionate measurement between corners ½ mile N, S, E, and 1 mile W. Could not definitely identify U.S. evidence or anything for previous corner.
 - K-8 Found square cedar stake at corner, apparently used in other surveys and fits measurement to good corner south.
 - K-9 Found cedar stake faced by stumps with old hack marks, probably established in old county surveyor's survey. Appears to have been widely accepted, and fits pattern of survey. Possible U.S.B.T. evidence.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-7	K-8	K-9
DNR Mon. & Red top post	DNR Mon. & Red top post	Set DNR Mon.
9" R. Oak N45W 32.3'	6" Bl. Ash N30E 25.0'	12" Leaning Cedar N72E 38.0'
8" Beech Clump	8" Cedar S78E 50.85'	5" Tamarack N28W 40.6'
(4 trunks) N74W 4.35'		*20" W.P. Stp. N55W 6.8'
30" W.P. Stp. S20E 21.4'		*14" W.P. Stp. S40E 12.8'
Approx. Old Fence Cor.		
N40E 18'		*Old NBT's.


SIGNED BY Kenneth J. Ostling DATE 8/6/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____