

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CLARE
(County)

Located in: _____ Corner Code ##

- | | | |
|------------------------------------|----------------------------|-----------------|
| 1. Public Land Survey | T <u>20N</u> R <u>3W</u> | <u>A-1, B-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>4</u> T _____ R _____ | <u>1</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, C.F. ROSER, in a field survey on MAY, 6, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1	B-1	1
-----	-----	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 FD CONSERVATION DEPT MON. COMMON TO SEC 6, T20N-R3W, AND SEC 1, T20N-R4W. SET BY K.J. OSTLING, 6-22-66. FD REMAINS OF BOTH KJO WIT'S. KJO ESTABLISHED THIS COR ON THE 2ND CORRECTION LINE AT U.S. RECORD MEASUREMENT EAST OF STANDARD TWP. COR. TO T21N-R3 & 4W, WHICH IS 8.35 CHAINS WEST. EL'Y EDGE OF TAG ALDER SWP IS EAST 105' ± 10'.	B-1 FD CONSV. DEPT. MON. FOR N1/4 COR SEC 6, T20N-R3W. K.OSTLING SET THIS COR BY PROPORTIONATE MEAS. BETWEEN RESPECTIVE SECTION CORNERS OF SEC 6. CTR OF E-W TRAIL IS 16' S. CTR OF N-S TRAIL IS 129' E. FD 1 1/2" PIPE N84°E, 139.0'.	1 ESTABLISHED NE COR OF FRL. NW 1/4 OF FRL. NW 1/4 OF SEC 6, PER STANDARD BLM INSTRUCTIONS. EAST EDGE OF SWP. IS 105' ± 15' EAST.
--	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 FD CONS. DEPT. MON, ADDED CEDAR POST. 2" BALSAM S60°E 34.5' 2" MAPLE S30°E 46.2' 5" MAPLE S05°W 42.6' 7" MAPLE S50°W 53.2'	B-1 FD CONSV. DEPT. MON. AND ADDED CEDAR POST. 3" MAPLE N80°W 23.0' 11" J. PINE N05°E 8.3' 7" MAPLE N20°E 18.1' 8" MAPLE S20°E 28.7' 8" MAPLE (CLP) S40°W 28.7'	1 DROVE 3/8" X 66" GALV. PIPE W/LS CAP & SET CEDAR POST WITH LOC. TAG. 6" CEDAR N80°W 14.8' 11" CEDAR S55°E 19.9' 6" CEDAR S20°E 20.8' 10" CEDAR S70°W 26.4'
--	--	--



Signed by Carl F. Roser * LS K.OSTLING WIT. * LS, K.OSTLING WIT. Date 3-29-94

Surveyor's Michigan License No. 12028