

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970
Clare County Remonumentation

For Corners In:
Clare Located In _____ Corner Code # _____
(County)

1. Public Land Survey	T	<u>20N</u>	R	<u>3W</u>	<u>C4</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	R	_____	_____
	S	_____	R	_____	_____
3. Miscellaneous Property in Section	S	_____	R	_____	_____
	S	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 14 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C4 - GLO - Set 1/4 post - G.E Adair -1856
W. Pine 24" N63°E 19 L.
W. Pine 13" S67°E 29 L.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C4 - 1/4 Cor. Common to Sec. 7 & 8, T20N, R3W - No conclusive GLO evidence found. Set 4" DNR Alum. Cap on 1" X 36" Galv. Iron pipe by single proportion to GLO between 'C3' & 'C5'. Center line of N-S 2-track is 28' W. Set DNR Mon. accepted as a careful & faithful re-established of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C4 - 4" DNR Alum. cap on 1" X 36" Galv. Iron pipe
Set Blue Carsonite Post 1' E
N15°W 9.02" to set Nail & Tag in W. side 18" R. Maple scribed 'XBT'
N61°E 30.96" to set Nail & Tag in N side 3" R. Oak scribed 'XBT'
N20°E 35.66' to set Nail & Tag in E side 19" W. Oak scribed 'XBT'
S40°W 7.31' to set Nail & Tag in N side 2" W. Pine

- 4" DNR Mon. used and accepted in place of Clare Co. Remon. Mon.



Signed by: Craig W. McVean Date: 8/27/2003

Surveyor's Michigan License No.: 39088

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		● 8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													