

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Clare _____
 (County)

1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S 32 T 20N	R 3W	9
	S 32 T 20N	R 3W	16
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

1. Craig W. McVean, in a field survey on Oct. 13, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:
 9 - None
16 - CSR - L. 4, p. 147 - A. D. Johnson - 1908
 Pine 24" S64°E 105
 - North Central Survey Co. - Proj. # 76144
 L. Cavanagh - 1976 - Set 1/2 x 18" Steel Bar
 2.2' S. of CL. of Rd.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 9 - CE 1/16, Sec. 32 - Set 2" Alum. Cap on 5/8" x 34" Rebar 16 - E 1/16 Common to Sec. 32, T20N, R3W and Sec. 5, T19N, R3W - No evidence of Cavanagh irons in Rd. or N. ROW - Probably obliterated during road reconstruction.
 Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. CL of E-W Bit. Rd. is 2.5' N. Fence Line S is 2± W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 9 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar. 16 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar.
 N80°E 5.27' to set N & T in S side 6" R. Maple
 N20°E 14.48' to set N & T in NW side 11" Cedar
 S20°E 29.58' to set N & T in E side 12" Cedar
 N76°W 18.07' to set N & T in S side 9" Hemlock
 Set blue carsonite post w/ loc. tag 1' SE

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/3/2003

