

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Clare (County) _____

1. Public Land Survey T _____ R _____
 T _____ R _____
 2. Property Controlling S 12 T 20N R 4W 7
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

1. Craig W. McVean, in a field survey on Sept. 9, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
 Z - CSR - L. 5, p.264
 Poplar 5" S70°W 33 L.
 Poplar 4" N11½°E 20½ L.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Z - N 1/16 Cor. Common to Sec. 12, T20N, R4W and Sec. 7, T20N, R3W -
 Couldn't find any conclusive evidence of old corner or BT's - Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure - Down 0.5' of CL. N-S Gravel Rd. is 4.5' W. Fence line E. is 1.5' ± S. Down remains of Fence to West.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Z - 2" Alum. Cap on 5/8" x 34" iron rebar
 Set blue carsonite post w/ loc. tag 33' West
 N81°E 27.65' to set N & T in N. side 10" Oak
 S62°W 63.01' to set N & T in NW side 4" Oak
 N65°W 33.73' to set N & T in N. side 16" R. Maple
 S75°W 62.05' to set N & T in N. side 9" R. Maple

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/3/2003