

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
CLARE (County)

- |                                      |           |         |         |
|--------------------------------------|-----------|---------|---------|
| 1. Public Land Survey                | T _____   | R _____ | _____   |
|                                      | T _____   | R _____ | _____   |
| 2. Property Controlling in Section   | S 4 _____ | T 20N   | R 3W    |
|                                      | S 4 _____ | T 20N   | R 3W    |
|                                      |           |         | 11      |
| 3. Miscellaneous Property in Section | S _____   | T _____ | R _____ |
|                                      | S _____   | T _____ | R _____ |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Aug 27, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		5		5		4		3		2			1
3						4							
4						8		9		10		11	12
5													
6						18		17		16		15	14
7													13
8						19		20		21		22	23
9													24
10						30		29		28		27	26
11													25
12													
13						31		32		33		34	35
													36

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- 10 - None 11 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 10 - S 1/16 Corner common to Section 4 & 5  
Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure.
- 11 - SW 1/16 corner common to Section 4  
Set 2" Alum Cap on 5/8" x 34" rebar per standard BLM procedure.  
West 56'± to CL. 2-track  
South 91'± to CL. 2-track

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 10 - Set stamped 2" Alum. Cap on 5/8" x 34" rebar  
Set blue carsonite post 1' SW  
S10°E 1.89' to set N & T in NW side 7" Oak  
S79°W 28.43' to set N & T in SE side 4" W. Pine  
N10°W 18.87' to set N & T in SW side 6" W. Pine  
N76°E 27.90' to set N & T in N side 16" Oak
- 11 - Set stamped 2" Alum Cap on 5/8" x 34" rebar  
Set blue carsonite post 1' SW  
S02°W 41.74' to set N & T in W side 6" W. Pine  
S88°E 38.90' to set N & T in S side 4" W. Pine  
N34°E 20.77' to set N & T in NW side 4" Cherry  
N84°W 42.96' to set N & T in N side 8" W. Pine

Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 12/3/2003