

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Clare Located In _____ Corner Code # _____
 (County)


1. Public Land Survey	T	R		
	T	R		
2. Property Controlling in Section	S 4	T 20N	R 3W	9
	S 4	T 20N	R 3W	15
3. Miscellaneous Property in Section	S	T	R	
	S	T	R	

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

1. Craig W. McVean, in a field survey on Sept. 3, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3						4							
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													



A. Description of original monument and accessories and/or subsequent restoration:
 9 - None 15 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 9 - CE 1/16th corner, Section 4. Set 2" Aluminum Cap on 5/8" x 34" rebar per standard BLM procedure.
 8' North to Centerline of trail E-W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 9 - 2" Aluminum Cap on 5/8" x 34" rebar. 15 - 2" Aluminum Cap on 5/8" x 34" rebar.
 Set Blue Carsonite Post 1' SW
 Set Blue Carsonite Post 1' NW
 S63°E 7.60' to set N & T in NE, side 5" White Pine
 S11°W 32.69' to set N & T in E, side 15" White Pine
 S70°W 17.04' to set N & T in S, side 15" Triple W. Oak
 N10°E 45.38' to set N & T in W, side 8" White Pine
 N74°E 9.29' to set N & T in NW, side 3" Red Maple
 N34°W 31.56' to set N & T in W, side 3" Red Maple
 N22°E 5.40' to set N & T in SE, side Twin 3" Red Maple
 S05°W 11.90' to set N & T in E, side 3" Red Maple

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/3/2003

Register of Deeds Stamp & File Number