

# LAND CORNER RECORDATION CERTIFICATE

## Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County) \_\_\_\_\_

1. Public Land Survey T 20N R 3W F11  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_  
 5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Oct. 15, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- F11 - GLO - Set 1/4 Post - G. Adair - 1856  
 W. Pine 20" N60°E 19 L.  
 Hemlock 11" S33°W 25 L.  
 - CSR - L. 3, p. 25 - A. D. Johnson - 1953  
 Gov't. Pine Stp. 28" N40°E 9 L.  
 Tw. Maples 8" N2°E 76 L.  
 "F11" to "G11" - 40.50 CH  
 - Rec. Sur. - L. 2, p. 715-718  
 C. E. Ostling - 1982  
 Set 1/2" bar M. P. O. L. from above  
 corners (Sec. Corners E & W). Nail 8" Ash  
 East 18.6'; Nail 5" Maple South 8.75'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F11 - ¼ Corner Common to Sec. 28 & 33 - Fd. ½" x 18" iron rebar and 2 witnesses per Rec. Survey. No conclusive evidence of GLO or Johnson BT's or corner noted by Johnson. A ½" smooth iron rod was found lying flat Ely 5± of Ostling ½" iron. N40°E 9± to fd. tipped up pine stp. remains but disturbed by Log Rd. construction. CL. of Log Rd. W. is 26± N and Log Rd. S is 34± E. Also looked for evidence of Johnson's E 1/16 Cor. - ¼ mile E, but nothing conclusive found. Measured grid distance East of 2670.24' vs. 2673' - ADJ. 2674.4' - CEO. Measured West grid distance 2672.96' vs. 2674.4' - CEO to fd. Iron 'L' fence post and ½" iron noted as "E11" by Ostling. 1/2" iron set by C. E. Ostling is acceptable as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F11 - Replaced ½" x 18" iron rebar w/ stamped 2" Alum. Cap on 5/8" x 3/4" iron rebar in ring of stones.  
 Set orange carsonite post 1' N  
 East 18.73' to set N & T in S. side 14" Ash (CEO)  
 S9°E 8.85' to set N & T in W. side 11" R. Maple (CEO)  
 S51°W 22.68' to set N & T in SE side 14" R. Maple  
 N25°W 16.78' to set N 7 T in E. side 4" R. Oak



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/3/2003