

SURVEY & REMONUMENTATION

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>20N</u> R. <u>5W</u>	<u>M-5</u>
	T. <u>20N</u> R. <u>4W</u>	<u>A-5</u>
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

199900007859
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 09-20-1999 At 11:15 am.
 LAND CORNER 9.00
 OR Liber 2 Page 23 - 23

Instrument Liber Page
 199900007859 OR 2 23

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on August 25, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This is a single common corner to
 T20N, R5W, M-5 and T20N, R4W, A-5

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1-76 Ostling LCRC #241
 Fd 1/2" iron bar, origin unknown, that seems to fit occupation in Sec 7.
 Probably established in connection with gravel pit but can find no record of same. Set DNR monument & red-top post.
 S80W 21.6 5" J. Pine
 S43E 10.1 6" J. Pine

1838 Nicholson, Set Post Cor. Sec. 12 & 13
 Pitch Pine 10, N13W 17
 Pitch Pine 9, N60W 12

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul S. Leph
 Date 9-15-99

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 See dossier for detailed report.

Found DNR Monument and witness post. Found one 1976 witness. Meas. approximately 2628' West to L-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Accepted DNR Monument for Clare County Remonument. Accepted as best available evidence of the accepted position of the corner.
 Witnesses:

N74°W 14.81 Set N & T in 10" J. Pine
 S50°E 10.35 Set N & T in 12" J. Pine (OBT)
 N18°W 23.82 Set N & T in 8" J. Pine
 N70°E 21.91 Set N & T in 8" J. Pine



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 9-15-99