

CLARE County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 # 265-98  
 98 NOV 18 AM 9:54  
 REGISTER OF DEEDS  
 CLARE COUNTY  
 CAROL A. MCAULAY

For corners in

CLARE Located in: Corner Code #  
 (County)

1. Public Land Survey T20N R04W D-13  
 T19NR04W D-1  
 T R  
 T R  
 2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on June 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to T20N, R04W  
 D-13 and T19N, R04W D-1

A. Description of original monument and accessories and/or subsequent restoration:

D-13: 1838 Nicholson GLO  
 Set 1/4 Sec Post  
 Wit-Y. Pine 8 S88 1/2E 62  
 Y. Pine 10 S77 1/2E 56

11-08-46 F.McClung 2-46  
 Plat of Airport Forest Subd. No. 2

9-20-78 Lapham LCRC#322  
 Set 1/2" C.I. in Found Mon Box  
 Wit-same as (132) 2-317

1-14-80 Lapham  
 References corner in unrecorded survey

**SURVEY &  
 REMONUMENTATION**

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13: Corner has been removed but three 1977 witnesses were still there. Reset corner from data on unrecorded survey of 1980. Re-established corner fit 1977 witness trees. Measured West 2650.37' to Section Corner. Measured East 2646.41' to Section corner.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13: Set 5/8" x 36" rod with Clare Co. Remon. Cap marked P.S.#27458. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 S10W 35.00', nail & tag, 22" R. Oak  
 N55E 11.38', nail & tag, 17" R. Oak (OBT)  
 East 24.43', nail & tag, 16" R. Oak (OBT)  
 S45W 12.40', nail & tag, 16" R. Oak (OBT)



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul A. Lapham  
 Date 9-22-98

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458

Date 11-16-98