

**SURVEY & REMONUMENTATION**

JAN 14 1999

CLARE County Remonumentation

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 # 299-98

98 NOV 24 AM 10:23

For corners in SECTION

CLARE (County)	Located in:	Corner Code #
1. Public Land Survey	T20N R04W T19N R04W	F-13 ✓ F-1
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
CLARE COUNTY  
CAROL A. McAULAY

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on October, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

This is a single corner common to  
T20N, R04W, F-13 and T19N, R04W, F-1

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
	18		17		16		15		14		13		
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

F-13: 1838 Nicholson GLO  
Set 1/4 Post  
Aspen 6 N63W 14  
Aspen 12 S6-1/2E 31

circa 1900 Unknown  
S. Pine 18 S82W 21  
S. Pine 18 N88E 34

10/30/47 F. McClung, Airport Subdivision No. 3, Plat of West 1/2 of Southwest 1/4 Sec 33 2-49

7/20/55 Norton, Harrison Woods. 4-15  
Plats N-S 1/4 line

May, 1962 Lapham

Two unrecorded surveys shows 1" iron pipe at intersection of extension of West line of Supv. Plat of Harrison Woods. (Platted N-S 1/4 line) with North line of section. Corner falls 2640 feet East of E-13 and 2601 feet West of G-13.

N34E 28.5 12" Oak  
N85E 19.2 4" Oak  
S78W 5.61 11" Oak

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F-13: Found 3/4"X26" pipe. Measured East 2598.87 feet to G-13. Measured West 2639.81 feet to E-13. Found concrete plat monument on section line 1286.73 (platted 1287) feet East of E-13. Found one 1962 witness.

See dossier for detailed information

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-13: Set 5/8"X36" re-rod with Clare Co. remon cap marked PS 27458. Accepted as best available evidence of the accepted position of the corner.

S18W 4.66 Nail & Tag in 17" R. Oak  
S80W 5.65 Nail & Tag in 16" W. Oak (OBT)  
S49E 38.45 Nail & Tag in 12" Maple clump of 5  
N25W 35.85 Nail & Tag in 17" W. Oak



**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County

Chairman Paul S. Lapham  
Date 10-20-98

Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 11-23-98